

REQUEST FOR TENDER

Package M132 – Heaters Package

Kalium Lakes Potash Pty Ltd (Company) along with EPCM Contractor DRA Pacific Pty Ltd (DRA) are requesting tender bids to be involved as part of the Beyondie Potash Project located approximately 160 km south east of Newman, Western Australia. Details of the project can be found in <http://www.kaliumlakes.com.au/beyondie-potash-project>

The scope of the package for **Heaters Package** is to include:

- Three (3) sets of external heaters, attached to two bins and one chute. Duties require the heater to maintain product temperature of about 60°C to 70°C. Heaters are to be designed to start with full bin/chute.
- One (1) screw-in immersion heater, attached to side of tank. The heater requires to heat fluid from 50°C to 80°. The tank will be attached with an agitator, supplied by other vendors, to distribute the heat.
- All heaters shall comprise with complete assemblies with all associated components required to produce a fully operational system.
- All fasteners, gaskets, packers, shims and any other items necessary for site assembly.
- Refer to Equipment Datasheet P082-2000-DSH-ME-012 & P082-2270-DSH-ME-022, for further details and extensive list of inclusions and requirements.
- Design to conform to the relevant Australian Standards and Statutory requirements.

The Company plans to issue a formal request for pricing during the week commencing 01st May 2020, with closure of submissions scheduled for the 15th May 2020. To obtain full bidder documents please submit your details to the following email address: Shoki.Harada@draglobal.com